BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK_INDENT53020

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/13/2022-23, Date: 23-08-2022

Name of Work:Flood relief work in Netaji nagara and surrounding areas in ward no. 07, Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B Girish	
				In Figures	In Words
1	110.03	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead I By Manual Means B Cement Concrete Grade M-15 & M-20	Cum	731.7	Rupees Seven Hundred Thirty One and Seventy Paise Only
2	17.87	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead (iii) Dismantling Stone Masonry B Rubble stone masonry in cement mortar.	Cum	481.5	Rupees Four Hundred Eighty One and Fifty Paise Only
3	382.59	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.	Cum	186.2	Rupees One Hundred Eighty Six and Twenty Paise Only
4	104	Construction of Embankment by excavating the available approved Gravel/Murrum deposited at a place or borrow pits during or prior excavation with all lifts and lead, transportation to site, spreading,grading to required slope and compacting to meet the requirement complete as per specifications, including cost of labour,rolling,water,all materials,usage& all other appurtenaces required to complete the work.	Cum	402.4	Rupees Four Hundred Two and Forty Paise Only
5	65.19	Providing and laying in position plain cement concrete Mix 1:3:6 (M10) for levelling course for all works in foundation. Using 40 mm nominal size graded crushed coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications.	Cum	5559.6	Rupees Five Thousand Five Hundred Fifty Nine and Sixty Paise Only
6	132.35	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M20 (The cost of steel reinforcement & formwork to be paid separately)	Cum	6272.7	Rupees Six Thousand Two Hundred Seventy Two and Seventy Paise Only
7	8.46	Supplying, Fitting and Placing TMT Fe550 bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications.	Tonne	92262.2	Rupees Ninety Two Thousand Two Hundred Sixty Two and Twenty Paise
8	299.25	Providing and Fixing pre cast covering Slab 100mm thick made out of CC , Jelly 20mm Down Size with steel reinforcement including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete as per Engineer incharge. (Data Rate)	Sqm	1885.5	Rupees One Thousand Eight Hundred Eighty Five and Fifty Paise Only
9	47.64	Providing and Fixing pre cast covering Slab 230mm thick made out of CC , Jelly 20mm Down Size with steel reinforcement including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete as per Engineer incharge. (Data Rate)	Sqm	4583.67	Rupees Four Thousand Five Hundred Eighty Three and Sixty Seven Paise Only
10	510	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 5.5 m3)	Cum	118.12	Rupees One Hundred Eighteen and Twelve Paise Only
11	653	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km.	t.Km	96.1	Rupees Ninety Six and Ten Paise Only

B Girish

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92